



City of Moore Oklahoma

301 N. Broadway, Moore, OK 73160 | (405) 793-5000 | www.cityofmoore.com

NOTICE TO PROCEED

DATE: December 2, 2015
TO: Rudy Construction
PROJECT: Plaza Towers Street Repair
I-02-W-URG

The City of Moore has considered the budget submitted by you for the above referenced project.


You are hereby notified the budget has been accepted in the amount of \$2,761,074.01.


You are required to return an acknowledged copy of Notice to Proceed to the City of Moore.

Dated this 2nd day of December, 2015.

By: 
Stan Drake, Assistant City Manager

ACCEPTANCE OF NOTICE

Receipt of the foregoing Notice to Proceed is hereby acknowledge by 
this 2 day of December, 2015.

By: 

Title: President

City of Moore - ON DEMAND SERVICES - W.O. #I-02-W-URG (Plaza Towers Street Repair)

OKC Spec	Pay Item	Description	Unit	Unit Price	Est. Qty	Total
200	00	Unclassified Excavation (>500 C.Y.)	C.Y.	\$ 15.00	11335	\$ 170,025.00
213	01	Crushed Rock Foundation	C.Y.	\$ 70.00	5135	\$ 359,450.00
304	04	Portland Cement Concrete Pavement (6")(>500 S.Y.)	S.Y.	\$ 55.00	18015	\$ 990,825.00
305	00	Curb & Gutter (2'-8")(6" Barrier)(>500')	L.F.	\$ 20.00	14198	\$ 283,960.00
812	02	Remove Curb & Gutter	L.F.	\$ 7.00	10748	\$ 75,236.00
812	03	Concrete Pavement Removal	S.Y.	\$ 10.00	12850	\$ 128,500.00
813	00	Remove Driveway	S.Y.	\$ 10.00	2973	\$ 29,730.00
820	01	Sawcut Pavement	L.F.	\$ 4.00	650	\$ 2,600.00
823	00	Sidewalk (5')	S.Y.	\$ 55.00	667	\$ 36,685.00
823	03	6" P.C. Conc. Driveay (HES)	S.Y.	\$ 65.00	2973	\$ 193,245.00
824	01	Temporary Surface Course (TBSC)	Ton	\$ 40.00	364	\$ 14,560.00
840	04	Solid Slab Sodding (U-3 Bermuda)	S.Y.	\$ 3.00	6420	\$ 19,260.00
453	00	Reinforced Concrete Pipe (18 Inches)	L.F.	\$ 70.00	175	\$ 12,250.00
454	34	Design 2-0 Inlet Complete in Place	Ea.	\$ 4,000.00	1	\$ 4,000.00
454	63	Grated Street Inlet (26' Wide)	Ea.	\$ 17,500.00	2	\$ 35,000.00
811	16	Structure Removal (Concrete Flume) RCP	L.F.	\$ 15.00	745	\$ 11,175.00
740	09	Construction Barricades (Type III)	S.D.	\$ 10.00	1800	\$ 18,000.00
740	10	Warning Lights (Type A)	S.D.	\$ 1.00	3600	\$ 3,600.00
740	14	Channelizers Cones	S.D.	\$ 1.50	9000	\$ 13,500.00
453	04	Reinforced Concrete Pipe (48 Inches)	L.F.	\$ 240.00	570	\$ 136,800.00
454	30	Junction Box (6' x 6') - 3ea	C.Y.	\$ 850.00	9	\$ 7,650.00
		Mailbox Remove & Replace	EA	\$ 500.00	54	\$ 27,000.00
		Survey & Staking, as needed	EA	\$ 1,250.00	5	\$ 6,250.00
		CCTV Inspection	LF	\$ 2.00	571	\$ 1,142.00

Mobilization \$ 180,631.01

Estimated Total This W.O. \$ 2,761,074.01